



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission  
CONSERVATION DIVISION  
(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED February 19, 1963  
STATE CORPORATION COMMISSION

MAR 4 1963

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Art Lamb of Lamb Casing Pulling Co. has this

date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Frank Jones

Complete Address: Box 387, McPherson, Kansas

Lease Name: Dick Estate Well No. 1

Location: SW NW NE Sec. 21 Twp. 20 Rge. 9 (E) (W) X

County Rice Total Depth 3282 1/2 Oil Well

Gas Well    Input Well    SWD Well    D & A X Lost Hole   

Mr. Lamb was instructed to plug the well as follows:

Fill hole with sand to 2970' and cement with 5 sacks.


Fill hole with mud to 185'. Set rock bridge from 185'

to 175' and cement with 20 sacks. Fill hole with mud to

40'. Set rock bridge from 40' to 30' and cap hole with

10 sacks cement.

Very truly yours,

  
Conservation Division Agent