



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

May 16, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent) STATE CORPORATION COMMISSION

RECEIVED
MAY 25 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. John Glen of Pipe Pullers, Inc. has this date requested permission to plug the following described well:

Mr. Glen guarantees payment of the plugging fee.

Operator's full Name: Sterling Drilling Company

Complete Address: Box 129, Sterling, Kansas 67579

Lease Name: Fair "H" Well No. 1

Location: E/2 E/2 NW Sec. 24 Twp. 20 Rge. 9 (E)(W) X

County: Rice Total Depth 3330' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Glen was instructed to plug the well as follows:

Fill hole with sand to 3300' and cement with 4 sacks cement.

Fill hole with mud to 228'. Set rock bridge from 228' to 220' and

cement hole with 15 sacks cement. (7" surface casing) Fill hole with

mud to 35'. Set rock bridge from 35' to 25' and cap hole with 5 sacks

cement.

Very truly yours,


Conservation Division Agent