

State of Kansas



FORM - CP-2
Rev. 6-26-62

15-159.03783.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ, Commissioner
HARRY G. WILES, Commissioner
RAYMOND B. HARVEY, Secretary
ROBT. C. LONDERHOLM, Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

November 13, 1963

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. William Orr of Thunderbird Drilling Inc. has this date requested permission to plug the following described well:

Mr. Orr guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling Inc.

Complete Address: 712 Union Center, Wichita, Kansas

Lease Name: Seitz Well No. 5

Location: SW SE SW Sec. 24 Twp. 20 Rge. 9 (E) (W) X

County Rice Total Depth 3435' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. ORR was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 200'. Push
Plug and $\frac{1}{2}$ sack hulls to 200' and cement with 20 sacks
through drill pipe. Fill hole with mud to 40'. Push
plug and $\frac{1}{4}$ sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,