



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

September 30, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wilbur Crandall of Knight Casing Pulling Co, Inc. has this date requested permission to plug the following described well:

Mr. Crandall guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Inc.

Complete Address: Box 18112, Wichita, Kansas 67218

Lease Name: Seitz Well No. 1

Location: SW SW SW Sec. 24 Twp. 20 Rge. 9 (W) (O)

County: Rice Total Depth 3368' Oil Well (G)

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Crandall was instructed to plug the well as follows:

Fill hole with sand to 3350' and cement with 5 sacks cement.

Fill hole with mud to 210'. Set rock bridge from 210' to 200' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set

rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


Conservation Division Agent