

15.139.00491.0000

**KANSAS**  
**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
**STATE CORPORATION COMMISSION**

APR 19 1962

**CONSERVATION DIVISION**  
**Wichita, Kansas**

**TO:**  
**J. P. Roberts**  
**Assistant Director**  
**500 Insurance Building**  
**212 North Market**  
**Wichita 2, Kansas**

File No. \_\_\_\_\_ County: Rice

Location: \_\_\_\_\_ SW- SW- SE- Sec. 24 Twp. 20 Rge. 9 ~~(E)~~ (W)

Name of Field: Wild Cat Total Depth: 3500'

I have this date completed supervision of plugging of:

Lease Name: Schwamborn Well No. I

Operator's Full Name: Carl Libsack & Morgan, et al

Complete Address: P.O. Box 479 Hays, Kansas

Plugging Contractor Isern Wells

Address: P.O. Box 486 Ellinwood, Kansas License No. Rotary

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No X

If Yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 7:PM Day 15 Month 4 Year 62

The above well was plugged as follows:

Filled hole w/36 vis mud from T.D. 3500' back to 225' set a halco plug 1/2 sak hulls and  
ran 25 sax cement from 210' back to 135' . Filled hole w/ 36 vis mud from 135' back to  
30' set a halco plug and ran 8 sax cement from 25' back to zero 4' below ground level.  
8 5/8" surface pipe 4' below ground level. Filled rat hole w/ mud and 2 sax cement 3'  
below ground level.

Signed: Coalm Jones  
Conservation Division Agent

Reviewed: Harold Hollis  
Field Supervisor

Remarks:

**INVOICED**  
DATE 4/26/62  
INV. NO. 4844-W