

15.159.00631.0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1962

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sterling Drilling Company

Complete Address: Box 127, Sterling, Kansas

Lease Name Fair "G" Well No. 1

Location NW NW NW Sec. 24 Twp. 20 Rge. 9 (E) (W) X

County Rice Total Depth 3430'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Operator

Address: License No.

Operation Completed: Hour 6:30 AM Day 16 Month August Year 1962

The Above well was plugged as follows:

Heavy mud circulated. Hole filled with mud to 200'. Plug and 1/4 sack
hulls pushed to 200' and cemented with 20 sacks thru drill pipe.

Hole filled with mud to 35'. Plug and 1/4 sack hulls pushed to 35' and
hole cemented to bottom of cellar with 10 sacks.

Rathole bridged, and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 8/20/62

INV. NO. 5560-W