

1060116

TO: STATE CORPORATION COMMISSION

8-13

API NUMBER 15-135-24,059.0000
W/2 W/2 SE NW SEC. 21, T 19 S, R 25 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM NORTH SECTION LINE
 WICHITA STATE OFFICE BLDG., 130 S. MARKET 1485 FEET FROM WEST SECTION LINE
 WICHITA, KANSAS 67202 LEASE NAME DINGES C WELL # 1
 TECHNICIAN'S PLUGGING REPORT COUNTY NESS 148.37
 OPERATOR LICENSE # 5086 WELL TOTAL DEPTH 4565 FEET
 OPERATOR: PINTAIL PETROLEUM, LTD PRODUCTION CSG: SIZE " FEET
 NAME AND 225 N MARKET, SUITE 300 SURFACE CASING: SIZE 8 5/8" FEET 252'
 ADDRESS WICHITA, KS 67202
 ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X
 OTHER WELL AS HEREINAFTER INDICATED
 PLUGGING CONTRACTOR MALLARD JV INC LICENSE NUMBER 4958
 ADDRESS P.O. BOX 1009 McPHERSON, KS 67460-1009
 COMPANY TO PLUG AT: HOUR: 12:45 PM DAY: 13 MONTH: 08 YEAR: 1998
 PLUGGING PROPOSAL RECEIVED FROM DON
 (COMPANY NAME) MALLARD JV INC (PHONE) 316-241-4640

WERE:
1ST PLUG AT 1850' WITH 50 SX CEMENT, 2ND PLUG AT 900' WITH 80 SX CEMENT,
3RD PLUG AT 270' WITH 40 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT,
5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,
6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT

8-20-98

RECEIVED
 KANSAS CORP COM
 1998 AUG 20 A
 11 10

PLUGGING PROPOSAL RECEIVED BY MIKE MALERS
 PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE
 OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 13 MONTH: 8 YEAR: 1998
 ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE
1ST PLUG AT 1850' WITH 50 SX CEMENT, 2ND PLUG AT 900' WITH 80 SX CEMENT,
3RD PLUG AT 270' WITH 40 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT,
5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,
6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL 1/4 FLO SEAL BY ALLIED
 (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID OBSERVE THIS PLUGGING.

DATE 8-21-98

SIGNED Michael J. Malers
 (TECHNICIAN) FORM CP-2/3

INV. NO. 31187