

To: 6 061363  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3536  
Operator: Ramco Drilling Service Inc.  
Name & Address Box 99  
Belpre, Ohio 45714

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D. S. and W Well Service License Number 6901  
Address Box 2311 Claflin, Kansas 67525

Company to plug at: Hour: 10:00 AM Day: 28 Month: Oct. Year: 19 87

Plugging proposal received from Bob Strube  
(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

were: Order 100 sks 65/35 Pozmix 10% Gel 2% Econolite 5 sks Hulls.

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:45 AM Day: 28 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT 8 5/8" set at 260' w/190 sks, 5 1/2" set at 3521' w/125 sks.

Top perf at 2850'. Plugged bottom w/sand and 5 sks cement to 3330'. Shot pipe one

(1) time and recovered 2800'. Pumped in 8 5/8". 5 sks Hulls, 100 sks cement w/600 Psi.

RECEIVED  
STATE CORPORATION COMMISSION

11-12-87 NOV 12 1987

Remarks: By Halliburton  
(If additional description is necessary, use BACK of this form)  
WICHITA, KANSAS

~~Observe this plugging.~~

**INVOICED**  
DATE 10-23-87  
INV. NO. 18948

Signed Gilbert G. Scheck  
(TECHNICIAN)  
Gilbert G. Scheck