

12-28-87

6 061393

009-23,835 . 0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SW _____, SEC. 18, T 20 S, R 13 W/EX
1650 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8538
Operator: Bibs Oil Corp
Name & Address: Box 1436
Great Bend, Ks. 67530

Lease Name Harrison Well # 1
County Barton 117.00
Well Total Depth 3600 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 761

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050
Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 9:30AM Day: 28 Month: Dec Year: 19 87

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2457

were: Order 125 sks 65/35 Poz 10% Gel 2% Econolite 5 sks Hulls.

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:50AM Day: 28 Month: Dec Year: 19 87

ACTUAL PLUGGING REPORT 8 5/8" set at 761' w/385 sks. 5 1/2" set at 3599' w/175 sks.
Top perf at 3522'. Plugged bottom w/sand and 5 sks cement to 3470'. Shot pipe 3 times
and recovered 2176'. Pumped in 8 5/8" 25 sks cement w/5 sks Hulls in 100 sks cement w/800
Psi.

Remarks: By Halliburton
(If additional description is necessary, use BACK of this form.)

(If desired, you may observe this plugging.)

DATE 1-11-88

INV. NO. 19475
12-28

1-7-88
Signed Gilbert G. Scheck (TECHNICIAN)
Gilbert G. Scheck

STATE CORP. DIV.
JAN 07 1988