

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

APT NUMBER 15- 809-21,867
NW, Sec. 8, T 20S, R 13 WE
1650 feet from NS section line
990 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Niolet Well # 1

Operator: Raymond Oil Co.
Name & Address: One Main Place, Suite 900,
Wichita, Mo. 67202

County Barton

Well Total Depth 3565 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 763'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Logging Pulling License Number 6050

Address PO-Box 126, Chase, Mo. 67924

Company to plug at: Hour: 3:00 PM Day: 15 Month: 12 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Mike Kelso

(company name) Kelso Logging Pulling (phone) 316-938-2457

were: Order 165 lbs. 50% port mix - 4% Gel - 37 gal. H., 5 sacks hulla,
15 sacks Gel. + 8 5/8" plug.

Signed Ruth L. Schell
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:00 PM Day: 15 Month: 12 Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" 763' sp. sec. w/ 450 sacks cement, 5 1/2" set at
3564' w/ 150 lbs cement. Top perf. at 3210'. Plug back to 3520'.
Plug bottom w/ 5 sack cement, sand & 5 sack cement to 3150'. Slot pipe 3
times & recovered 2215'. Pumped into 8 5/8" sp., 25 sack cement, 4 sacks
hulla, 12 sacks Gel., 50 sack cement, 3 sacks Gel., 1 sack hulla, released
plug & followed w/ 90 sack cement.

Remarks: Maximum pressure 1000 pounds.

RECEIVED
STATE CORPORATION COMMISSION

12-21-82 DEC 21 1982

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

INVOICED
DATE 12-28-82
INV. NO. 2064-W

Signed Ruth L. Schell
(TECHNICIAN)