

062063

1-16

284

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19-009.30185.0001

NE, SEC. 7, T 20 S, R 13 W/4E
4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Lease Name Russell-Brewer Well # 1

Operator: Edmiston Oil Co., Inc.
Name & Address: 125 N. Market
12060 KSB and T Bldg. St. 1260
Wichita, Ks. 67202

County Barton 115.38
Well Total Depth 3550 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 768

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase Ks. 67524

Company to plug at: Hour: 10:00 AM Day: 16 Month: Jan Year: 19 90

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2943

were: Order 300 sks 60/40 poz 8% gel 5 sk shulls.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:00PM Day: 16 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8" set at 768' w/ sks. 5 1/2" set at
w/ sks. Top perf at 3341'. Plugged bottom w/ sand and 5 sks cement to
3290'. Shot pipe two times and recovered 2500'. Pulled 5 1/2" casing to 1300' and spotted
100 sks cement. Pulled casing to 900' and spotted 100 sks. Pulled casing to 400' and
spotted 100 sks cement to surface, w/ 500 psi. Squeezed. Used 300 sks cement.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: By Allied. JAN 26 1990 1-26-90

(If additional description is necessary, use BACK of this form.)

INVOICED
FEB 05 1990

CONSERVATION DIVISION
Wichita, Kansas

Signed Gilbert G. Scheck
(TECHNICIAN)

DATE

INV. NO. 27323

Gilbert G. Scheck