

4-060742

SEP 26 1995

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- 12-26-62

W2 SE SW /4 SEC. 12, 20 S, 13 W  
660 feet from S section line  
3630 feet from E section line

Operator license# 7383

Lease: Teichman Well # 1

Operator: Grady Bolding Corporation

County: Barton 112.13

Address: 114 N. Main  
Ellinwood, Kansas 67526

Well total depth 3450 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 202 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: D.S. & W. Well Servicing, Inc. License# 6901

Address: P.O. Box 231 - Claflin, Kansas 67525

Company to plug at: Hour: 12:00 A.M. Day: 26 Month: September Year: 1995

Plugging proposal received from:

Company: D.S. & W. Well Servicing, Inc. Phone: 316-587-3361

Were: Order 205 sxs 60/40 posmix - 10% gel and hulls.  
Plug while pulling casing.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 1:00 P.M., Day: 26, Month: September, Year: 1995

Actual plugging report: 8 5/8" to 202' with 200 sxs. 5 1/2" to 3446' with 125 sxs. Perfs at 3258' - 3262'. Sanded to 3200' and spotted 5 sxs cement. Discovered that well had been squeezed and no pipe could be recovered. Cut casing at 685' and 1500'. Tied onto production casing and pumped 130 sxs cement with 500# hulls. Max. P.S.I. 1500#. S.I.P. 200#. Tied onto annulus and pumped 16 sxs cement with pressure lockup.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Allied Cementing.

10-6-95 OCT 6 1995

Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES  CALC  NO  Dakota plug: YES  NO   
Plugged through TUBING , CASING . Elevation: 1847 GL

I did  observe the plugging.

*[Signature]*  
AT (agent)

INVOICED  
DATE OCT 10 1995  
INV. NO. 43714