

6 050225

API NUMBER 15-009 23 503

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

N 1/2 - Sec 12, T 20 S, R 13 (W 4)

_____ feet from S section line

_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6670

Lease Name Parish Well # 1-B

Operator: Black Bird Oil Co.

County Barton 119.44

Name & Address Box 1584

Well Total Depth 3675 feet

Great Bend Kans
67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 300 - exc 275 1/4

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Enterprise License Number 5111

Address Great Bend Kan.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Heenan Pully

(company name) Rockhold Ent (phone) _____

were: Order 170 sac 60/100 Pay mix 6% Gel 3% CC. 5 sac hulls 8 5/8 Plug.
T.D. 3675 - 8 5/8 @ 300 w 275 sac - 5 1/2 @ 3639 w 200 sac
Elev: @ 1851 - Perfs. 3275 - 3275

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 P Day: 16 Month: Sept Year: 1985

ACTUAL PLUGGING REPORT

Sand to 3220 w 5 sac cement dumped with
dump trailer - shot 5 1/2 at 2400' and recovered same.
Attached 8 5/8 Plug container to 8 5/8 surface pipe and pumped
4 sac hulls - 25 cement - 12 sac Gel - 40 sac cement - 3 sac Gel
1 sac hulls - Released Plug and squeezed with 105 sac cement
with 800 lbs working pressure and 500 lbs standing Press.

Remarks: Cemented by B. J. Titon
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE SEP 24 1985

INV. NO. 10220

RECEIVED
STATE CORPORATION COMMISSION
Gilbert P. Luika
(TECHNICIAN)

SEP 23 1985
9-23-85
CONSERVATION DIVISION