

6010445  
70' W N/2 N/2

API NUMBER 15-009-24143.0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE, SEC. 24, T. 20 S, R. 13 W/B  
2310 feet from S section line  
1390 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Schermuly Well # 2-24

Operator: Texas Energies Inc.  
Name & Address: Box 947  
Pratt Ks.

County Barton 115.38

Well Total Depth 3550 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 700

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Wheatstate oilfield svc. License Number 5149

Address Pratt Ks.

Company to plug at: Hour: 2:10 AM Day: 9 Month: 1 Year: 19 86

Plugging proposal received from Mark Stevenson - Ted Moff

(company name) Texas Energies (phone) \_\_\_\_\_

were: Lost circulation.

OVER

Plugging Proposal Received by D.F.B.  
(TECHNICIAN)

Plugging Operations attended by Agent? All Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:05 PM Day: 10 Month: 1 Year: 19 86

ACTUAL PLUGGING REPORT

OVER

Remarks: Halliburton com. co.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
JAN 30 1986

DATE \_\_\_\_\_

INV. NO. 12191

STATE CORPORATION COMMISSION  
JAN 27 1986  
CONSERVATION DIVISION  
WICHITA, KANSAS

Signed Walter Butcher  
(TECHNICIAN)  
1-21-86

26  
1-19-86

Anhydrite 682-702 Arbuckle 3502

Elev. 1851 No Dakota

From 700 - to 3109 Drilled 9 7/8 hole

From 3109 to 3550 Drilled 7 7/8 hole

Lost Circ. Zone 2771-91

Salt Section 1170-1640

Well was plugged as follows:

Pumped 25 sx. Cm. @ 3500 60/40 Pozmix 6% Gel.

Pulled pipe to 2460

Pumped 50 sx Cm. @ 2460 60/40 Pozmix 6% Gel 3% c.c.

Pulled pipe to 2160 Let set 2 hrs.

Pumped in 54 Bbls. Mud. Did not circulate.

Pumped 50 sx. Cem 60/40 pozmix 6% Gel 4% C.C. 1 sx. Flocele.

Pulled pipe to 1560 Let set 2 hrs.

Pumped in 50 Bbls. Mud Did not circulate.

Pulled Pipe, ran in Halliburton # EZSC

Retainer plug. Tried to set @ 2676 - 2606 - 2546 Would not set.

Pulled and found plug was ruined.

Ran in Halliburton E 2 Bridge plug. Could not get below 2230 - Set plug @ 2168

Ran drill pipe to 2080 circulated with mud.

Pumped in 50 sx. Cement 60/40 Pozmix, 6% Gel 3% C. C.

Pulled Pipe to 1700

Pumped in 25 sx. Cemt. 60/40 Pozmix 6% Gel.

Pulled pipe to 1100.

Pumped in 25 sx. 60/40 Pozmix 6% Gel.

Pulled pipe to 720

Pumped in 100 sx. Cem. 60/40 Pozmix 6% Gel.

Laid down pipe Pushed plug to 40.

Pumped in 15 sx. Cement 60/40 Pozmix 6% Gel.

Pumped 15 sx. in rat hole 10 sx in mousehole.

*Dale F. Balthazor*

Dale F. Balthazor

38-20-1

11/21