

15.145.20023.0000

Form CP-3  
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

SEP 25 1967

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name O. A. Sutton

Complete Address: 800 Sutton Place Wichita, Kansas

Lease Name Archbold Well No. 1

Location C SE SE Sec. 4 Twp. 20 Rge. 20 (E)     (W) X

County Pawnee Total Depth 4380'

Abandoned Oil Well     Gas Well     Input Well     SWD Well     D & A X

Other well as hereafter indicated:    

Plugging Contractor: Gabbert-Jones, Inc.

Address: Wichita, Kansas License No.    

Operation Completed: Hour 5 P Day 23 Month 9 Year 1967

The Above well was plugged as follows:

RTD 4380' 8 5/8 csg set at 505' cwc 335 sc.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 35 sc cem.

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Lowell Massey  
Well Plugging Supervisor

DATE 9/26/67

INV. NO. 6388-U