

K

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 25 1977

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 145 - 20,455 . 0000 (of this well)

Operator's Full Name C & G Drilling Co.

Complete Address 1107 Douglas Bldg., 104 S. Broadway, Wichita, Kansas

Lease Name Fox Well No. 3

Location Approx C W/2 SE SW Sec. 4 Twp. 20 Rge. (E) (W) 20

County Pawnee Total Depth 4364'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 6:45 P Day 23 Month 2 Year 1977

The above well was plugged as follows:

RTD 4364' 8 5/8 cwg set 252' cwc 130 sx. Flg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 2-25-77

INV. NO. 4687-W