

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 29 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 4th National Bank Bldg., Wichita, Kansas

Lease Name Ashley "B" Well No. 1

Location C NE SE Sec. 34 Twp. 20 Rge. 23 (E) (W) X

County Ness Total Depth 4450

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor:      Co. Tools     

Address:      License No.     

Operation Completed: Hour 8:45 A Day 27 Month 3 Year 1968

The Above well was plugged as follows:

RTD 4450' 8 5/8 csg set at 255' cwc 160 sc/  
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sc cem.  
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Mearns  
Well Plugging Supervisor

INVOICED

DATE 3/29/68  
INV. NO. 7491-W