

15.135.20362.0000

Form CP-3  
Rev. 6-4-68

KANSAS

*ll*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 17 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company

Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name Byron Well No. 1

Location C NE NW Sec. 34 Twp. 20 Rge. (E) (W) 23

County Ness Total Depth 4410

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Strata Drlg.

Address Wichita, Ks. License No.     

Operation Completed: Hour 5 A Day 13 Month 8 Year 1970

The above well was plugged as follows:

RTD 4410' 8 5/8 csg set at 287' cwc 170 sf. Cmt. Mat. 50-50 poz 5% gel.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Mansuy  
Well Plugging Supervisor

DATE 8/17/70

INV. NO. 2398-W