

15.009.19453.0000

Form CP-3
Rev. 6-26-62

40
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1962

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Alpine Oil & Royalty Co., Inc.

Complete Address: 800 Bitting Bldg., Wichita, Kansas

Lease Name Aldrich Well No. # 1

Location SE SW NW Sec. 36 Twp. 20 Rge. 13 (E) (W)

County Barton Total Depth 3525

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glenn & Smith Pipe Pulling Co.

Address: 204 E. 6th., Ellinwood, Kansas License No. 396

Operation Completed: Hour 1 PM Day 16 Month 12 Year 1962

The Above well, was plugged as follows:

8 5/8" 260' Gwc.

Sanded hole back to 3290' & dumped 4 sax cement with dump bailer.

Pulled pipe, bailed hole down to 260', set rock bridge, & displaced

25 sax cement. Mud to 40', set rock bridge, & displaced 10 sax cement,

cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 12-26-62

INV. NO. 6286-W