

Wichita, Kansas
CONSERVATION DIVISION

DEC 8 - 1950

DISTRICT CONSERVATION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 38-22

LOCATION nw-sw-nw

SEC. 36 TWP. 20 RGE. 13-w

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Aldrich

Operator Wetgate-Greeland Oil Co. Address 1022 N. N. Bldg. Wichita, Kans.

Field _____ County Barber

Total Depth 3274 Feet.

(Describe briefly the manner in which the well was plugged)

Surface hole 8 3/4 - 285 ft. Circulated with cement.
4" casing set at 3246 ft. Cemented with 100 sacks cement.
Plugged back to 3240 ft with mud & Chat -
dumped 5 sacks of cement at 3240 ft. Picked off
& pulled the 4" casing - mud to 285 ft. Set Rock
Bridge & 14 sacks of cement at 285 ft. Mud to 30 ft
plus 10 sacks of cement at the surface -
Bill Morgan - Plugging Contractor

PLUGGING
FILE SEC 36 T 20 R 13w
BOOK PAGE 38 LINE 27

C. M. Stough
District Conservation Agent

Date 12-4-50