

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW-SW-NW

SEC. 36 TWP. 76 RGE. 13-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Aldrich

Operator Westgate-Asseculand Oil Co address 1022 N. N. B. Bldg. Wichita-Kans.

Field \_\_\_\_\_ County Barton

Total Depth 3308 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2-290 ft. Circulated with cement.  
5 1/2 casing set at 3305 ft. Cemented with 100 sacks cement.  
Plugged back to 3300 ft. with chat. Dumped 5 sacks  
of cement at 3300 ft. Ripped off & pulled the  
5 1/2 casing. Went to 290 ft. Set Rock Bridge  
& 15 sacks of cement at 290 ft. Went to  
30 ft. Plug & 10 sacks of cement at  
the surface.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 18 1950

CONSERVATION DIVISION  
Wichita, Kansas

C. R. Stovall  
District Conservation Agent

Date 12-14-50

**PLUGGING**  
FILE SEC 36 TWP 76 R 13W  
BOOK PAGE 38 LINE 23