

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 1241-42

LOCATION W. W. S. W.

SEC. 36 TWP. 20 RGE. 13-w

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Schultz

Operator Wichita-Granland Oil Co. Address 1009 Central Bldg. Wichita-Kans.

Field _____ County Barton

Total Depth 3545 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 283 ft. Circulated with cement.
5 1/2 casing set at 3475 ft. - 75 sacks of cement. Plugged
back to 3240 ft. with mud & chert. Dumped 5 sacks of
cement at 3240 ft. - killed off & pulled the 5 1/2 casing
mud to 283 ft. Set Rock Bridge & 10 sacks of
cement at 283 ft. - mud to 35 ft. - Bridge &
10 sacks of cement at the surface.

Bill Morgan - Plugging Contractor

RECEIVED
STATE CORPORATION COMMISSION

JAN - 9 1952

CONSERVATION DIVISION

Carl Stogard
District Conservation Agent

Date 1-7-52

PLUGGING
FILE SEC 36 TWP 20 R 13-w
SACK PAGE 124 LINE 42