

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 129-35

LOCATION SW-SW-NE

SEC. 31 TWP. 20 RGE. 15 W

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Harms

Operator H-H Supply Co Address Box 4173 Okla City Okla

Field \_\_\_\_\_ County Barton

Total Depth 3828 Feet.

Plugging Contractor Forbes Casing Pulling Co

Plugging Contractor's License No. 49

Address Great Bend Kas.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 7/8" @ 1019' c.w.c. Oil string 5 1/2" o.d.  
set 3820' w/ 75 st cem. Filled hole with sand  
to 3810' and dumped 5 st cem. Shot off and  
pulled 5 1/2" casing. Filled hole with mud to  
300' set rock bridge and run 20 st cem.  
mud to 35' rock bridge and 10 st cem to  
base of cellar

**PLUGGING**  
FILE SEC 31 TWP 20 R 15  
PAGE 29 LINE 35

**RECEIVED**  
STATE CORPORATION COMMISSION  
MAY 10 1954  
CONSERVATION DIVISION  
Wichita, Kansas

Warren H. Horner  
District Conservation Agent  
Date May 6, 1954