

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 117-45

LOCATION SE 1/4 NE 1/4 SE

SEC. 31 TWP. 20 RGE. 16-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 5 Lease Houdershell

Operator Phillips Peten Co. Address Box # 779 - St. David - Kans.

Field _____ County Barton

Total Depth 3820 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 999 ft. Circulated with cement
5 1/2" casing set at 3818 ft - 100 sacks of cement
Mixed 5 sacks of cement on bottom of hole - shot off
& pulled the 5 1/2" casing - mud to 250 ft. Set back
bridge & 15 sacks of cement at 250 ft. mud
to 35 ft. Bridge & 10 sacks of cement at
the surface -
The Well Supply Co. - Plugging Contractors

STATE COM. 11-20-51 NOV 20 1951

C. M. Stough
District Conservation Agent

Date 11-18-51

PLUGGING CONSERVATION DIVISION
Wichita, Kansas
FILE SEC. 31 T. 20 R. 16 W
BOOK PAGE 117 LINE 45