



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Hitting Building
Wichita, Kansas

FILE NO. 57-10

LOCATION NE-7E-SW

SEC. 31 TWP. 20 RGE. 19-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Houdersshell

Operator Auderson-Richard Oil Co. Address Box #142 - St. Paul - Kans.

Field _____ County Barton

Total Depth 3834 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 1015 ft. Circulated with cement.
5 1/2" casing at 3830 ft. - Cemented with 100 sacks cement.
Plugged back to 3810 ft with shot - Dumped 5 sacks
of cement at 3810 ft - Shot off & pulled the 5 1/2" casing
head to 300 ft - Set Rock Bridge & 15 sacks of cement
at 300 ft. head to 30 ft - Plug & 10 sacks of
cement at the surface.
Hooker Casing Pulling Co. Plugging Contractor

RECEIVED
STATE CORPORATION COMMISSION

1-27-51 JAN 27 1951

C. M. Stouffer
District Conservation Agent

Date 1-25-51

PLUGGING
FILE SEC 31 TWP 20 R 15W
BOOK PAGE 57 LINE 10