

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 43-17

LOCATION 5/4 - NESWSE

SEC. 31 TWP. 26 RGE. 15E

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Houdeshell

Operator Phillips Petco Co Address Box #779 - G. Beard - Kans.

Field _____ County Barton

Total Depth 3819 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 1006 ft. Circulated with cement.
5th casing set at 3819 ft. Cemented with 125 sacks cement
Small Wells Plug at 3776 ft. Filled hole with chert from
3776 ft to 3765 ft. Rigidized 5 sacks of cement at 3765 ft.
Shot off & pulled the 5th casing - Mud to 250 ft. Set
Arch Bridge & 15 sacks of cement at 250 ft. Mud to 30 ft
Bridge & 10 sacks of cement at the surface -
West Supply Co. - Plugging Contractors

RECEIVED
STATE CORPORATION COMMISSION

DEC 12 1950
PLUGGING
CONSERVATION DIVISION
Wichita, Kansas
FILE SEC 21-10-17
BOOK PAGE 43 LINE 17

C. D. Stough
District Conservation Agent
Date 12-7-50