

13

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 117-44

LOCATION SE 1/4

SEC. 31 TWP. 10 RGE. 15.00

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 4 Lease Houdyshell

Operator Phillips Petco Co. Address Box #779 G. Beard - Haces-

Field _____ County Barton

Total Depth 3809 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 988 ft. Circulated with cement.
5 1/2" casing set at 3803 ft. 200 sacks of cement.
Annulled 5 sacks of cement on bottom of hole.
Shot off & pulled the 5 1/2" casing - mud to 250 ft -
Set Rock Bridge & 15 sacks of cement at 250 ft -
mud to 35 ft - Bridge & 10 sacks of cement
at the surface -

The West Supply Co. - Plugging Contractors

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1951 11-14-51

CONSERVATION DIVISION

W. M. Powell
District Conservation Agent

Date 11-11-51

PLUGGING
FILE SEC-3 (T 20 R 152)
BOOK PAGE 117 - LINE 44