


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 125-19

LOCATION SW-22W-2E

SEC. 31 TWP. 20 RGE. 15 or

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Harves

Operator Anderson-Prichard Oil Corp. Address Box 142 - H. Beach - Kans.

Field _____ County Barber

Total Depth 3889 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 1015 lb. Circulated with cement.
5 1/2 casing set at 3825 lb - 175 sacks of cement. Pumped
6 sacks of cement on bottom of hole. Shot off & pulled
the 5 1/2 casing - mud to 250 lb. Set Rock Bridge &
15 sacks of cement at 250 lb - mud to soft. Bridge
& 20 sacks of cement at the surface -

Forbes Casing Pulling Co. - Plugging Contractors

RECEIVED
STATE CORPORATION COMMISSION

11-26-51 NOV 26 1951

CONSERVATION DIVISION
Wichita, Kansas

C. D. Storch
District Conservation Agent

Date 11-23-51

PLUGGING
FILE SEC 31 T 20 R 50
BOOK PAGE 15 LINE 19