

2

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 126-29

LOCATION SW-SE-11W

SEC. 31 TWP. 10 RGE. 15-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Gilbert

Operator Anderson-Richard Oil Co. Address Box #142 G. Bend. Kans.

Field _____ County Barton

Total Depth 3836 Feet.

(Describe briefly the manner in which the well was plugged)

Surfact Pipe 8 1/2" - 1026 lb. Circulated with cement.
5 1/2" casing set at 3828 lb. - 150 sacks of cement. Plugged
back to 3820 with Chat. - Mixed 15 sacks of cement
at 3820 lb. Shot off & pulled the 5 1/2" casing - mud
& 230 lb. Set back. Bridge & 15 sacks of cement
at 230 lb. mud to 350 lb. Bridge & 10 sacks
of cement at the surfact.
Forbes Casing Pulling Co. - Plugging Contractors

PLUGGING
FILE SEC 31 T 20R 15W
BOOK PAGE 126 LINE 29

11-30-51
NOV 30 1951
C. H. Stouch
District Conservation Agent

Date 11-28-51