


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Flat

Barton County. Sec. 31 Twp. 20 Rge. 15(W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE/4 NE NW SE
Lease Owner Phillips Petroleum Company
Lease Name Houdyshell Well No. 5
Office Address Box 779, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil and Gas Well
Date well completed October 1, 1947
Application for plugging filed October 17, 1951
Application for plugging approved October 19, 1951
Plugging commenced November 14, 1951
Plugging completed November 18, 1951
Reason for abandonment of well or producing formation Uneconomical to operate.

If a producing well is abandoned, date of last production August 3, 1951
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough
Producing formation Arbuckle Depth to top 3769 Bottom 3820 Total Depth of Well 3820 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Heebner	Dry	3324	- -	8-5/8"	1000.20'	None
Brown Lime	Dry	3415	- -	5-1/2"	3840.34'	2641.00'
Lansing-Kansas City	Dry	3425	- -			
Conglomerate	Dry	3695	- -			
Viola	Dry	3701	- -			
Simpson	Dry	3734	- -			
Arbuckle	Oil & Gas	3769	3820			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped rock 3820' to 3818' - dumped 5 sx. cement in filling to 3790'. Mudded hole from 3790' to 250'. Set 10' rock bridge from 250' to 240'. Dumped 15 sx. cement in filling from 240' to 165'. Mudded hole to 35'. Set rock plug at 35' and dumped 10 sx. cement in filling to base of cellar. Well plugged and abandoned 4:00 PM. 11-18-51

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
A. J. Willis (employee of owner) ~~operator~~ of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) A. J. Willis

Box 779, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November, 1951

My commission expires November 18, 1953

Joseph M. Neal
Notary Public.



11-21-1951

15.009.16582-0000

Form No. 873

Formation Record

Lease Houdyshell

Well No. 5

FROM	TO	Formation	REMARKS
0	135	Clay	
135	705	Shale and shells	
705	980	Sand and shale	
980	987	Red Bed and Shells	
987	1000	Anhydrite	Set 8-5/8" casing at 997' RB
1000	1040	Anhydrite	
1040	1850	Shale and Shells	
1850	2840	Lime and shale	
2840	2920	Lime	
2920	3170	Lime and Shale	
3170	3225	Lime	
3225	3464	Lime and Shale	Top Heebner 3324' RB, Top Brown Lime 3415' RB.
3464	3598	Lime	Top L.K.C. 3425' RB.
3598	3683	Lime and Shale	
3683	3738	Lime	Top Conglomerate 3695' RB, Top Viola 3701' RB.
3738	3810	Shale and Lime	Top Simpson 3734' RB, Top Arbuckle 3769' RB.
3810	3818	Lime	Set 5-1/2" casing at 3818' RB.
	3820	TD	

PLUGGING
 FILE SEC-317-20 R/SW
 BOOK PAGE 47 LINE 45

RECEIVED
 STATE DEPARTMENT OF OIL
 NOV 21 1956
 CONGRESSIONAL RECORDS
 DIVISION