


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Barton County, Sec. 31 Twp. 20 Rge. 15 ~~#####~~(W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE SW
Lease Owner Anderson-Prichard Oil Corp.
Lease Name Houdyshell Well No. 2
Office Address Box 142 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed August 12, 19.47
Application for plugging filed January 22, 19.51
Application for plugging approved January 23, 19.51
Plugging commenced January 23, 19.51
Plugging completed January 26, 19.51
Reason for abandonment of well or producing formation Non-Commercial
If a producing well is abandoned, date of last production May 21 19.50
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Arbuckle Depth to top 3780 Bottom Total Depth of Well 3834 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	1013	None
				5-1/2	3830	2533'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole from TD to 3810 with crushed rock
Shot casing at 2533'.
Pulled casing and filled hole with heavy mud to 300'.
Set rock Bridge - Dumped 15 sax cement
Filled hole to 30' from top.
Dumped 10 sax cement for cap on well

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to W. J. Dearen of Anderson-Prichard Oil Corp.
Address Box 142 - Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Gerald M. Dougherty (employee of owner) or ~~owner~~ of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gerald M. Dougherty
Box 142 - Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 6 day of February, 1951

My commission expires December 4, 1954
Vernell M. Spilars Notary Public.

PLUGGING
FILE SEC 31 T 20 R 15W
BOOK PAGE 57 LINE 10

HOOBYSHELL WELL NO. 2

Location: C. NE. NE. SW. Section 31-20S-15W Barton County, Kansas
 Operator: The Day Petroleum Corporation
 Contractor: H. H. & B. Drilling Co., Inc.
 Commenced: 7-13-47
 Oil String Cemented: 7-27-47
 Total Depth: 3834'

Casing Record:	47 Jts. or 1015' 8-5/8" 8 RT 25.5% Surface Cemented @ 1015' with 375 sacks cement and 3 sacks Calcium Chloride.			
	Oil String - 113 Jts. 5-1/2" CD 14 8 RT Cemented @ 3830' with 150 sacks cement.			
		Anhydrite	1012	(+ 1004)
		Heobner	3347	(-1331)
		Base Groad	3379	(-1363)
		Brown Lime	3438	(-1422)
		Top White Lansing	3450	(-1434)
		Artuckle	3782	(-1766)

LOG

(Figures indicate bottom of formation)

Clay and sand	0 to 125
Shale	100
Shale	425
Shale and sand	450
Sand	550
Shale and red bed	780
Shale and red bed	955
Shale and red bed	1012
Anhydrite	1040
Shale and shells	1470
Shale and salt	1765
Shale and shells	1885
Lime and shale	2085
Lime	2255
Lime and shale	2355
Lime	2395
Shale and lime	2870
Lime	2970
Lime and shale	3450
Lime	3730
Conglomerate and shale	3765
Conglomerate	3779
Lime	3834
Total Depth	3834'

The undersigned, H. H. & B. DRILLING CO., INC., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

H. H. & B. DRILLING CO., INC.

BY: *[Signature]*
Asst. Secretary

Subscribed and sworn to before me this 30th day of July, 1947.

[Signature]
Notary Public

My commission expires: July 2, 1949.

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 1951
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 31 T 20R 152
LOCK PAGE 57 LINE 10