

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Barton County, Sec. 31 Twp. 20S Rge. 15 W. (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SE SW
Lease Owner Anderson-Prichard Oil Corporation
Lease Name Houdyshell Well No. 3
Office Address Box 112, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 22, 19 48
Application for plugging filed September 20 19 52
Application for plugging approved September 22 19 52
Plugging commenced September 28 19 52
Plugging completed October 5 19 52
Reason for abandonment of well or producing formation
Well non-commercial (100% water)
If a producing well is abandoned, date of last production July 1, 19 52
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Arbuckle Depth to top 3815' Bottom --- Total Depth of Well 3825' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1010'	None
				5-1/2"	3818'	2740'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PBD 3606' to 3473' - crushed rock and 5 sacks cement
Shot casing off @ 2740' - Pulled casing.
Squeezed with 25 sacks Aquagel and 200 sx. cement in surface pipe to surface

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Anderson-Prichard Oil Corporation
Address Box 112, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Gerald M. Dougherty (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gerald M. Dougherty District Clerk

Box 112, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 10 day of October, 19 52

My commission expires December 4, 1954

22-5133-5

9-49-10M

Wendell M. Hansen
RECEIVED
STATE CORPORATION COMMISSION
Notary Public.

PLUGGING
FILE SEC 31 T 20 R 15 26
BOOK PAGE 46 LINE 14

OCT 11 1952
CONSERVATION DIVISION
Wichita, Kansas
10-11-1952

HOUDYSHELL WELL NO. 3

Location: SW $\frac{1}{4}$ SE $\frac{1}{4}$ SW $\frac{1}{4}$ Sec. 31-20S-15W
Barton County, Kansas

Date Spudded: 2/8/48

Operator: Anderson-Prichard Oil Corporation

Date Rotary Completion: 2/25/48

Contractor: Heathman-Honaker Drilling Co.

Total Depth: 3819' Rotary

Surface Casing: 8 5/8ths " casing set at
1010' w/ 400 sacks cement.

Oil String: 5 1/2" casing (121 jts) set at
3818' cemented w/175 sacks cement.

LOG

(Figures indicate bottom of formation)

TOPS

(From Schlumberger)

Sand & shale	0 to 420	Lansing	3430
Dakota sand	520		
Dakota sand	545	Arbuckle	3773
Shale & shells	605		
Sand	660		
Red bed and shells	835		
Red Bed, shale & shells	995	Total Depth	3819'
Anhydrite	1010		
Anhydrite	1035		
Shale & shells	1470		
Shale	1830		
Lime & shale	1945		
Lime	2135		
Lime & shale	2675		
Lime, shells & shale	2790		
Shale & lime	3280		
Lime	3390		
Lime & shale	3438 3415		
Shale	3438		
Lime & shale	3486		
Broken lime	3543		
Lime	3685		
Lime & shale	3720		
Lime	3730		
Shaly conglomerate	3773		
Lime	3819 TD		

The undersigned, Heathman-Honaker Drilling Co., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above-noted well as reflected by the Daily Drilling Reports.

HEATHMAN-HONAKER DRILLING CO.

By Jack P. Heathman

Partner

Subscribed and sworn to before
me this 2nd day of March 1948.

John D. Bailey
Notary Public

My Commission Expires: January 30, 1952.

PLUGGING		
FILE	SEC 31 T 20 R 1524	
BOOK	PAGE 4	LINE 17

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas