


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton

County. Sec. 31 Twp. 20 Rge. 15 (#####) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SE SW
Lease Owner Anderson-Prichard Oil Corporation
Lease Name Houdyshell Well No. 1
Office Address Box 142 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed February 7, 19 47
Application for plugging filed Dec. 27, 19 50
Application for plugging approved Dec. 28, 19 50
Plugging commenced January 16, 19 51
Plugging completed January 24, 19 51
Reason for abandonment of well or producing formation Non-Commercial

If a producing well is abandoned, date of last production Nov. 16, 19 51
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Arbuckle Depth to top 3785 Bottom Total Depth of Well 3850 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1016'	none
				5-1/2"	3834'	3244'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with crushed rock to 3810'
Dumped in 5 sax cement
Shot casing off at 3244'
pulled pipe and filled hole with heavy mud to 300'
Set rock Bridge - dumped in 15 sax cement
Filled hole to 30' from top
mixed 10 sax cement for cap on well

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to W. J. Dearen, Anderson-Prichard Oil Corp.
Address Box 142 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Gerald M. Dougherty (employee of owner) or of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gerald M. Dougherty
Box 142 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6 day of February, 1951

My commission expires December 4, 1954 Verdella M. Hankins Notary Public.

PLUGGING
FILE SEC 31 T 20 R 15
BOX PAGE 52 LINE 9

HOUDYSHELL WELL NO. 1

Location: C. NE 1/4 SE 1/4 SW 1/4 Section 31-20S-15W Barton Co., Kansas Commenced: 12-21-46
 Operator: The Bay Petroleum Corporation Oil String Cemented: 1-11-47
 Contractor: H H & B Drilling Co., Inc. Total Depth: 3850'
 Casing Record: Surface Casing: 8-5/8" 32#, 8 Rd.Thd.33 jts. @ 1016'
 Cemented with 300 sacks-2 CC by Halliburton
 Oil String: 6-1/2" 8 Rd.Thd.14# 127 jts. @ 3834'
 Cemented with 100 sacks bulk cement by Halliburton

L O G

(Figures indicate bottom of formation)

Shale	0 to 200	Lime and shale	3005
Shale and shells	420	Lime and shale	3080
Sand	550	Lime and shale	3115
Shale and sand	595	Lime and shale	3180
Shale and shells	795	Lime	3220
Shale and lime	990	Lime	3255
Red bed	1010	Lime	3300
Anhydrite	1018	Lime and shale	3345
Anhydrite	1050	Lime and shale	3420
Shale	1210	Lime	3445
Shale	1460	Lime	3465
Shale and salt	1700	Lime	3507
Shale and lime	1845	Lime	3580
Shale and lime	1960	Lime	3615
Shale and shells	2020	Lime	3650
Lime	2040	Lime	3685
Lime and shale	2140	Lime and shale	3715
Lime and shale	2230	Lime and shale	3735
Lime	2285	Chert	3740
Lime	2330	Chert	3745
Lime and shale	2445	Lime	3780
Lime and shale	2500	Shale	3785
Lime and shale	2605	Shale and lime	3787
Lime and shale	2670	Arbuckle	3803
Lime and shale	2710	Arbuckle lime	3820
Lime and shale	2815	Arbuckle lime	3850
Lime and shale	2965		
Lime and shale	2955	Total Depth	3850'


The undersigned, H H & B DRILLING CO., INC., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

H H & B DRILLING CO., INC.

BY: Jack H. Heathman
 Vice-President

STATE OF KANSAS }
 COUNTY OF SEDGWICK }

SS:



Be it remembered that on this 20th day of January, 1947, before me, the undersigned, a Notary Public, duly commissioned, in and for the County and State aforesaid, came Jack H. Heathman, Vice-President of H H & B Drilling Co., Inc., a corporation of the State of Kansas, known to me to be such officer, and to be the same person who executed as such officer the foregoing instrument of writing in behalf of said Corporation and he duly acknowledged the execution of the same for himself and for said Corporation.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year first above written.

My commission expires: July 2, 1949.

Richard Lindley
 Notary Public