


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Barton County, Sec. 31 Twp. 20 Rge. 15 ~~XXXX~~ (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NW NE  
Lease Owner Anderson-Prichard Oil Corporation  
Lease Name Harms Well No. 2  
Office Address Box 142 - Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed April 23, 19 48  
Application for plugging filed November 19, 19 51  
Application for plugging approved November 20, 19 51  
Plugging commenced November 20, 19 51  
Plugging completed November 23, 19 51  
Reason for abandonment of well or producing formation Non-Commercial



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production November 19, 19 50  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough  
Producing formation Arbuckle Depth to top 3773 Bottom Total Depth of Well 3829 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	1015'	none
				5-1/2	3825	2650

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back from TD 3829 to 3771 w/6 sax cement  
Shot casing off at 2650' - Pulled Casing  
Filled hole with heavy mud to 250'  
Set permanent rock bridge & Dumped 15 sax cement  
Filled hole with heavy mud to 30' of top  
Mixed 10 sax cement for cap on well

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to W. J. Dearen, Anderson-Prichard Oil Corp.  
Address Box 142 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Gerald M. Dougherty (employee of owner) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Gerald M. Dougherty*  
Box 142 - Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of November, 19 51

My commission expires December 4, 1954

*Wesley M. Hopkins*  
Notary Public.

PLUGGING  
FILE SEC 31 T20 R50  
BOOK PAGE 128 LINE 19

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 30 1951  
CONSERVATION DIVISION  
Wichita, Kansas

ANDERSON-PRICHARD OIL CORPORATION

Drillers Log of Formation Encountered  
 NAME WELL #2  
 C. SW/4 NE/4 NE/4 Section 31-205-15W  
 Barton County, Kansas

FORMATION:	FROM	TO
Surface Clay & Sand	0	70
Sand & Shale	70	130
Redbed, Sand & Shale	130	135
Sand	135	555
Shale & Sand	555	625
Shale, Shells & Redbed	625	725
Shale & Shells	725	1000
Anhydrite	1000	1035
Shale & Shells	1035	1475
Salt & Shells	1475	1650
Shale & Shells	1650	1775
Shale & Lime	1775	1985
Lime	1985	2195
Shale & Lime	2195	2875
Lime	2875	3100
Lime & Shale	3100	3430
Lime	3430	3685
Lime & Shale	3685	3750
Shale	3750	3773
Lime	3773	3825
		Run 3825' 5-1/2" Casing & Cemented w/175 Sacks
Total Depth		3825

Date Started 2-15-48

CONTRACTOR: TRANSIT CORPORATION  
 Anco Tower  
 Oklahoma City, Oklahoma

I hereby certify the foregoing to be a true and correct driller's log of the formations encountered in the above well.

PLUGGING  
 FILE SEC 31-20-15W  
 PAGE 1 of 1  
 STATE

By Victor E. Davis  
 Victor A. Davis, Asst. Secy.

Certified to before me this 9th, day of March, 1948

Maxine Chambers  
 Maxine Chambers - Notary Public

NOV 30 1951  
 January 8, 1952  
 My Commission Expires