


15.009.21986.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely.
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County. Sec. 31 Twp. 20 Rge. 15 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
50' NW of NW NW NE
Lease Owner Woodman & Iannitti Drilling Co.
Lease Name Stoskopf Well No. 1
Office Address 1008 Douglas Bldg. 104 S. Broadway Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole



Locate well correctly on above Section Plot

Date Well completed Aug. 6 1980
Application for plugging filed Aug. 6 1980
Application for plugging approved Aug. 6 1980
Plugging commenced Aug. 6 1980
Plugging completed Aug. 6 1980
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3800
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1036	

Describe in detail the manner in which the well was plugged, indicating where the mud flu was placed and the method or methods used in introducing it into the hold. If cement or oth plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug 900' w/40 sx.
2nd plug 300' w/30 sx.
3rd plug 40' w/10 sx.

5 sx in rathole

RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1980

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Woodman & Iannitti Drilling Co.

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK
K. T. Woodman (employee of owner) or (owner or operat

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman
1008 Douglas Bldg. Wichita, Kansas 6720
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 19 80

My commission expires Feb. 11, 1984

Justina Chamberlain
Justina Chamberlain Notary Public.

15.009.21986.0000

K. T. WOODMAN
RES. PHONE 733-0418
OFF. PHONE 265-7650
WICHITA, KANSAS

D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors

1008 DOUGLAS BUILDING
104 S. BROADWAY
WICHITA, KANSAS 67202

August 11, 1980

Company;	Woodman & Iannitti Drilling Co.
Farm;	#1 Stoskopf
Location;	50' NW of NW NW NE
Section;	31-20-15W
County;	Barton
Contractor;	Woodman & Iannitti Drilling Co.
Comm;	July 30, 1980
Compl;	August 6, 1980
Total Depth;	3800
Casing;	8 5/8 @ 1036 w/450 sx.

Figures Indicate Bottom Of Formations;

225	Shale
280	Sand
445	Shale, redbed & sand
569	Dakota sand
745	Lime & shale
1036	Shale & sand
1064	Anhy
1354	Redbed & shale
2495	Shale & lime
3025	Lime & shale
3460	Lime & shale
3635	Lime & shale
3800	Lime & shale

I certify the above to be a true and correct copy of the drillers log to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.
K. T. Woodman
K. T. Woodman

RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1980
CONSERVATION DIVISION
Wichita, Kansas