

WELL PLUGGING RECORD


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Barton County, Sec. 31 Twp. 20S Rge. 15W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner H. & H. Supply Company
Lease Name Gilbert Well No. 5
Office Address P. O. Box 4173 Oklahoma City, Okla
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed May, 1948 19
Application for plugging filed September 17, 1953 19
Application for plugging approved September 18, 1953 19
Plugging commenced May 13, 1954 19
Plugging completed May 16, 1954 19
Reason for abandonment of well or producing formation oil depleted

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3860 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1032'	
				5-1/2"	3855'	2859'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled back from T. D. 3861' to 3840' with crushed rock and dumped 5 sacks cement. Shot casing off at 2859' - pulled casing out of hole. Bailed down to 300' - set permanent rock bridge and dumped 20 sacks cement - mudded to 35' and capped well with 10 sacks cement.
Work started 5-5-54; completed 5-16-54.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes dba/ Forbes Casing Pulling Company
Address P. O. Box 221 Great Bend, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Edward Shanley
Box 4173, Oklahoma City, Okla.
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of June, 1954

My commission expires 11/6/54

PLUGGING 7368-5 3-53-20M
FILE SEC 31 T 20 R 15W
BOOK PAGE 129 LINE 36

NOTARIED
Notary Public.
JUN 26 1954
CONSERVATION DIVISION
Wichita, Kansas

GILBERT WELL NO. 5

Location: NE $\frac{1}{4}$ NE $\frac{1}{4}$ NW $\frac{1}{4}$ Sec. 31-20S-15W
Barton County, Kansas

Date Spudded: 4-15-48

Operator: Anderson-Prichard Oil Corp.

Date Rotary completion: 5-3-48

Contractor: Heathman-Honaker Drilling Co., Inc.

Total Depth: 3860.5

Surface Casing: 33 jts. 8-5/8" casing set at
1032' and cemented with 450 sacks
bulk cement.

Oil String: 120 jts. 5-1/2" casing set at
3855' and cemented with 175 sacks
bulk cement.

LOG

(Figures indicate bottom of formation)

Shale	0 to	260	Lime	2870
Shale & sand		320	Lime & Shale	2945
Shale		450	Lime	3060
Sand		585	Lime & Shale	3469
Shale & Shells		725	Lime	3529
Shale		900	Broken Lime	3574
Shale & Red Bed		995	Lime	3595
Red Bed		1023	Lime & Shale	3755
Anhydrite		1070	Lime	3796
Shale		1605	Arbuckle Lime (coring	3860.5 TD
Shale & Shells		2005		
Lime		2240		
Lime & Shale		2300		
Shale		2465		
Shale & Lime		2848		

The undersigned, Heathman-Honaker Drilling Co., Inc., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

HEATHMAN-HONAKER DRILLING CO., INC.

BY

John P. Heathman

Subscribed and sworn to before me
this 7th day of May, 1948.

Richard Hindery
Notary Public

My commission expires July 2, 1949.

PLUGGING
FILE SEC 31-T 20 R 15W
BOOK PAGE 129 LINE 36

RECEIVED
STATE CORPORATION
MAY 10 1948
CONSERVATION
Wichita, Kansas