


WELL PLUGGING RECORD

Give Information Completely
Make Oath and Affidavit
Make Report to:
Conservation Division
State Corporation Commission
800 Blitt Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 31 Twp. 30S Rge. 15 ~~25XXX~~(W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SE NW
Lease Owner Anderson-Frithard Oil Corporation
Lease Name Gilbert Well No. 2
Office Address Box 142 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed November 10, 19 47
Application for plugging filed November 29, 19 51
Application for plugging approved November 30, 19 51
Plugging commenced November 30, 19 51
Plugging completed December 6, 19 51
Reason for abandonment of well or producing formation Non-Commercial

If a producing well is abandoned, date of last production August 31, 19 51
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough
Producing formation Arbuckle Depth to top 3794 Bottom Total Depth of Well 3846 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	1030'	none
				5-1/2	3839'	3021'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with rock from TD 3846 to 3830'
Dumped 5 sax cement with bailer. Top of cement 3790'
Shot casing off at 3021. Pulled casing
Filled hole with heavy mud to 250'
Set rock bridge, dumped 15 sax cement w/bailer
Filled hole with heavy mud to 35' of top
Mixed 10 sax cement for cap on well

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to W. J. Dearen, Anderson-Frithard Oil Corp.
Address Box 142 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Gerald M. Dougherty (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Gerald M. Dougherty*
Box 142 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of December, 19 51

My commission expires December 4, 1954

Verdella M. Hubkins
Notary Public.

PLUGGING
FILE SEC 31 T 30 R 15 W
BOOK PAGE 127 30230

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1951
CONSERVATION DIVISION
Wichita, Kansas

GILBERT WELL # 2

Location: Approx. Ctr. NE $\frac{1}{4}$ SE $\frac{1}{4}$ NW $\frac{1}{4}$ Sec. 31-20S-15W Date Spudded: 9-25-47
 Barton County, Kansas Oil String Cemented: 10-21-47

Operator: The Bay Petroleum Corporation Total Depth: 3848' (Rotary Table)

Contractor: H H & B Drilling Co., Inc. Elevation: 2028 DF
 2030 KB

Casing Record: Surface - 48 jts. or 1030.41' 8-5/8"
 8 V.Thd. 28# Casing
 Cemented with 325 sacks and 3 C.C. @ 1037'
 Oil String - 125 jts. 5-1/2" OD 14# H-40
 8 R.Thd. new casing (3861.83')
 Cemented with 125 sacks Dewey cement @ 3841'

T O P S (KB)

Anhydrite	1032 (-998)
Lansing	3458 (-1428)
Arbuckle	3794 (-1764)
Shale	3840 (-1810)
Total Depth	3848 (-1818)

L O G

(Figures indicate bottom of formation)

Clay and shale	0 to 141
Clay and shale	170
Shale and shells	425
Dakota sand	450
Dakota sand	575
Red bed and shale	1032
Anhydrite	1065
Red bed and shale	1200
Shale and shells	1450
Shale and salt	1785
Shale and shells	2065
Shale and lime	2180
Lime	2275
Lime and shale	2712
Shale and lime	2900
Broken lime	2915
Lime and shale	3090
Lime broken	3166
Lime	3235
Lime and shale	3495
Lime	3555
Lime and shale	3605
Lime	3750
Lime and shale	3820
Arbuckle lime	3848
Total Depth	3848'

The undersigned, H H & B DRILLING CO., INC., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

H H & B DRILLING CO., INC.

BY: Joe J. Honaker
 Vice-President

DEC 10 1951

Subscribed and sworn to before me this 25th day of October, 1947.

Wichita, Kansas

Richard Lindery
 Notary Public

My commission expires: July 2, 1949