


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Barton County, Sec. 31 Twp. 20S Rge. 15 ~~(E) XXXX(W)~~

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SE NW  
Lease Owner Anderson-Pritchard Oil Corporation  
Lease Name Gilbert Well No. 1  
Office Address Box 142 - Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed Sept. 17, 19 47  
Application for plugging filed November 24, 19 51  
Application for plugging approved November 26, 19 51  
Plugging commenced November 26, 19 51  
Plugging completed November 29, 19 51  
Reason for abandonment of well or producing formation Non-Commercial  
If a producing well is abandoned, date of last production October 29, 19 51  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough  
Producing formation Arbuckle Depth to top 3776 Bottom Total Depth of Well 3836 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	1026'	None
				5-1/2	3828'	2483

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back from TD 3836 to 3775 w/ 6 sax cement  
Shot casing off at 2483'. Pulled Casing  
Filled hole with heavy mud to 250'  
Set permanent rock bridge. - Dumped 15 sax cement  
Filled hole with mud to 30' of top.  
Mixed 10 sax cement for cap on well

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to W. J. Dearen & Anderson-Pritchard Oil Corp.  
Address Box - 142, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Gerald M. Dougherty (employee of owner, not owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gerald M. Dougherty  
Box 142 - Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of December, 19 51.

My commission expires December 4, 1954

Versella M. Jenkins  
Notary Public.

28-5091-s 8-50-10M  
FILE DEC 9 1951  
BOOK PAGE 124 LINE 29

STATE CORPORATION COMMISSION  
DEC 10 1951  
CONSERVATION DIVISION  
Wichita, Kansas

GILBERT WELL # 1

Location: Approx. Ctr. SW $\frac{1}{4}$  SE $\frac{1}{4}$  NW $\frac{1}{4}$  Sec. 31-20S-15W Barton County, Kansas Date Spudded: 8-17-47  
 Operator: The Bay Petroleum Corporation Oil String Cemented: 8-31-47  
 Contractor: H H & B Drilling Co., Inc. Total Depth: 3836'  
 Casing Record: Surface - 49 jts. of 1020' 8-5/8" used, 8 R.T. Elevation: 2016 DF  
 Cemented @ 1027' w/350 sack cement & 3 C.C. 2018 KB  
 Oil String - 129 Jts. of 3836.46' 5-1/2" 8 R.T.  
 J-55 Spang New Smls. @ 3030'  
 Cemented 6' off bottom w/150 sacks.

T O P S (KB)

Brown Lime	3439 (1421)
Lansing (White)	3452 (1434)
Arbuckle	3778 (2760)

L O G

(Figures indicate bottom of formation)

Clay and sand	0 to 80
Shale and shells	420
Dakota sand	565
Shale and shells and Red bed	847
Shale and red bed	1000
Shale and red bed	1017
Anhydrite	1029
Anhydrite	1045
Shale and shells	1350
Shale and salt	1760
Shale and lime	2200
Lime	2300
Lime and shale	3130
Lime	3345
Lime and shale	3420
Lime (3521-30 broken)	3560
Lime	3725
Conglomerate	3765
Lime and shale	3815
Lime (Arbuckle)	3836
Total Depth	3836'

The undersigned, H H & B DRILLING CO., INC., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.


H H &amp; B DRILLING CO., INC.

BY: J. J. Donahue  
Vice-President

Subscribed and sworn to before me this 2nd day of September, 1947.

Richard Hindery  
Notary Public

My commission expires: July 2, 1949



STATE OF KANSAS  
 DEC 10 1951  
 COMMISSIONER OF REVENUE  
 Wichita, Kansas