


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
2112 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Barton County, Sec. 4 Twp. 20 Rge. 13W (E) (W)  
Location as "NE/CNWXSWX" or footage from lines SW/SE/SW  
Lease Owner Forbes Casing Pulling Co.  
Lease Name Muir & Giles, Hoffman Well No. 1  
Office Address Box 221, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed Yes 19\_\_\_\_  
Application for plugging approved Yes 19\_\_\_\_  
Plugging commenced \_\_\_\_\_ 12-1 19 56  
Plugging completed \_\_\_\_\_ 12-6 19 56  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. R.M. Brundedge  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3405' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2826'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Measured into TD 3405'. Plugging started 12-1-56. Finished 12-6-56.  
Plugged off bottom with sand to 3395' and dumped 5 sacks cement.  
Shot 5 1/2" casing at 2826'. Pulled pipe out of hole and plugged well.  
Pumped in 25 sacks gel mud, 100 sacks cement and 3 sacks chloride.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 17 1956  
CONSERVATION DIVISION  
Wichita, Kansas  
12-11-56

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.  
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes  
Box 221 Great Bend  
(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of December, 1956 Kansas

My commission expires April 8, 1957  
Arthur F. Nichol Notary Public.

PLUGGING  
FILE SEC 4 T 20 R 13W  
BOOK PAGE 121 LI: E 1

WELL LOG.

HILLIARD W. MUIR  
2727 No. Main,  
Hutchinson, Kansas.  
and  
B. M. GILES,  
LARNED, KANSAS.

ELEVATION: 1856 R. B.  
COMMENCED DRLG: 12-10-55  
COMPL. DRLG: 12-21-55  
Production: Oil Well

CONTRACTOR: Welch & Olsson Drilling Co. Inc.

HOFFMAN #1  
SW SE SW of 4-20-13W, Barton County, Kansas.

Casing Record:

Set 276' of 8-5/8" with 175 sacks of cement.

(Figures indicate bottom of formations.)

<u>FORMATIONS:</u>	<u>DEPTHS</u>	<u>FORMATION TOPS.</u>
Shale	345	Anhydrite: 723 (Plus 1133)
Red Bed & Shell Strks:	700	Haebner: 3067 (-1211)
Red Bed:	723	Brown Lime: 3180 (-1324)
Anhydrite:	725 1/5	Lansing: 3192 (-1336)
Shale & Shells:	1755	RTD: 3405 (-1549)
Shale & Lime:	1915	
Lime & Shale:	2125	
Lime:	2190	
Shale & Lime:	2480	
Lime & Shale:	2885	
Lime:	3405. T. D.	

STATE OF KANSAS, )  
                          ) SS:  
SEDGWICK COUNTY, )

I hereby certify that the above is a true and correct copy of Drillers Log of well drilled in the approximate center of the SW SE SW of Section 4, Township 20 Range 13 West, Barton County, Kansas.

WELCH & OLSSON DRILLING COMPANY, INC.  
BY [Signature]  
R. R. WELCH

Subscribed and sworn to before me this 27th day of December, 1955.

[Signature]  
Notary Public.

My commission expires:  
June 12, 1959

PLUGGING  
FILE SEC 4 T 20 R 13W  
BOOK PAGE 121 LINE 1

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
Wichita, Kansas