


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Barton County, Sec. 4 Twp. 20 Rge. 13 (E) (W)

Location as "NE/CNW%SW%" or footage from lines SE SW SE  
Lease Owner Schermerhorn Oil Corporation  
Lease Name Campbell Well No. 1  
Office Address 714 First National Bldg., Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed 1-19-55  
Application for plugging filed 1-19-55  
Application for plugging approved 1-19-55  
Plugging commenced 1-19-55  
Plugging completed 2-9-55  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Red Harner  
Producing formation Depth to top Bottom Total Depth of Well 3545 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	757	8 5/8	Cemented	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3545 to 757 Mud  
757 to 667 Cement  
667 to 300 Mud  
300 to Bottom Cellar Cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor  
Address

STATE OF Oklahoma, COUNTY OF Tulsa, ss.  
Don E. Burkitt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
714 First National Bldg., Tulsa, Oklahoma  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of February, 19 55

My commission expires 10-20-57 [Signature] Notary Public.

RECEIVED  
FEB 21 1955  
CONSERVATION DIVISION  
WICHITA, KANSAS

PLUGGING  
FILE SEC 4 T 20 R 13W  
BOOK PAGE 26 LINE 24

SCHERMERHORN OIL CORPORATION

Campbell #1

SE SW SE, Sec. 4-20S-13W,  
Barton County, Kansas

Drilling Started 1-8-55  
Drilling Completed 1-19-55  
8 5/8 OD Casing Cemented @ 727'

<u>From</u>	<u>To</u>	<u>Formation</u>	<u>Remarks</u>
0	130	Sand	
130	300	Shale	
300	722	Red Bed	
722	740	Anhydrite	Ran 735' 8 5/8" Casing Set at 727. Cement w/ 400 sacks
740	1175	Shale	
1175	2891	Lime & Shale	
2891	3545	Lime	T.D. 3545 - Dry Hole

This is a certified true copy of the Driller's Log as shown on the Daily Drilling Reports.

*J.C. Carnahan*  
Badger Drillers, Inc.

Subscribed and sworn to before me this 10<sup>th</sup> day of February, 1955

*Oral Deakins*  
Notary Public

My Commission expires 10-20-57

RECEIVED  
DIVISION OF COMMISSION

FEB 15 1955

DIVISION  
OF COMMISSION

PLUGGING  
FILE SEC 4-20-13W  
BOOK PAGE 26 LINE 24