

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

BARTON County. Sec. 4 Twp. 20S Rge. 13W (#) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW

Lease Owner PETROLEUM, INC.

Lease Name PETROLEUM, INC. YARD Well No. 1

Office Address ROUTE 2, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) OIL

Date well completed FEBRUARY 12 19 55

Application for plugging filed OCTOBER 26 19 59

Application for plugging approved OCTOBER 28 19 59

Plugging commenced OCTOBER 29 19 59

Plugging completed NOVEMBER 3 19 59

Reason for abandonment of well or producing formation PRODUCIBLE ZONE

If a producing well is abandoned, date of last production SEPTEMBER 8 19 59

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well DONALD TRUAN, 634 SUNSET, RUSSELL, KANSAS

Producing formation KANSAS CITY Depth to top 3194' Bottom 3417' Total Depth of Well 3500 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		3206'	3210'	8-5/8"	239'	NONE
KANSAS CITY	WATER & LITTLE OIL	3216'	3220'	4-1/2"	3498'	2800'
		3275'	3285'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

(PLUGGED BACK TO 3320')

FILLED HOLE WITH CRUSHED ROCK FROM 3320'-3180'. RAN 4 SACKS OF CEMENT FROM 3180'-3141'. PUMPED IN 20 SACKS COMMERCIAL MUD. FILLED HOLE TO BASE OF WELL CELLAR WITH 100 SACKS OF CEMENT.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 25 1959

CONSERVATION DIVISION  
Wichita, Kansas

11-25-59

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor MORGAN WELL PLUGGING SERVICE

Address 102 WEST 18TH STREET

STATE OF KANSAS, COUNTY OF BARTON, ss.

DON SEARLE

(employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle

(Address)

SUBSCRIBED AND SWORN to before me this 18TH day of NOVEMBER, 19 59

Arthur J. Miles  
Notary Public.

My commission expires APRIL 14, 1963



# WELL LOG

15.009.15908.0000

COMP. Petroleum, Inc.

SEC. 4 T. 20S R. 13W

FARM YARD

NO. 1

LOC. SE SE SW


TOTAL DEPTH 3500'

COUNTY Barton County, Kansas

COMM. January 19, 1955.

COMP. January 28, 1955

CONTRACTOR Garvey Drilling Company



CASING 8-5/8" @ 239' w/175 sax.  
4 1/2" @ 3498' w/85 sax.

ELEVATION 1859' RB

PRODUCTION Arbuckle

FIGURES INDICATE BOTTOM OF FORMATIONS

175	Sand
265	Shale
715	Red Bed
735	Anhydrite
1530	Shale & Shells
1680	Shale, Shells & Lime
2595	Lime & Shale
2750	Shale & Shells
2965	Lime & Shale
3050	Lime
3185	Lime & Shale
3500	Lime
3500	RTD

Tops:

Heebner: 3066 (-1207)  
 Brown Lime: 3181 (-1322)  
 Lansing: 3194 (-1335)  
 Conglomerate: 3417 (-1558)  
 Arbuckle: 3477 (-1618)

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 25 1959  
 CONSERVATION DIVISION  
 Wichita, Kansas

State of KANSAS

County of SEDGWICK

ss:

I, Karl E. Becker of Petroleum, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the YARD #1 well.

*Karl E. Becker*

Subscribed and sworn to before me this 28th day of February, 19 55

My Commission Expires: 8-11-58

*[Signature]*  
NOTARY PUBLIC