

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County, Sec. 6 Twp. 20 Rge. 13 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE NW SE C-5/2 S/2 SE

Lease Owner E. K. Edmiston

Lease Name Waller Well No. 1

Office Address 501 First National Building Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed 1-18-66 19__

Application for plugging approved 1-20-66 19__

Plugging commenced 1-31-66 19__


Plugging completed 3-14-66 19__

Reason for abandonment of well or producing formation _____

Dry

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3523 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	760	None
				4 1/2	None	1708

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cleaned out cellar. Rigging up unit.

Sanded off bottom to 3500' with 4 sacks.

Shot pipe at 3000'. Sun Oil Well Cementing, Inc. spotted oil.

Shot pipe at 2700' - 2552' - 2328' and 2037'.

Working pipe. Shot pipe at 1900' - 1800' and 1700'. Pulling pipe.

Cleaned out cellar. Cut off head. Welded on 8 5/8 collar. Shut in water.

Sun Oil Well Cementing, Inc. squeezed well with 100 sacks of cement and 25 sacks of mud. Well completed.

RECEIVED
STATE CORPORATION COMMISSION

MAR 17 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes

P. O. Box 221 Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of March, 19 66

My commission expires May 27, 1969

[Signature]
Notary Public.

DRILLER'S LOG

Company: E. K. Edmiston/
501 First National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced: June 2, 1965

Rotary Drilling Completed: June 9, 1965

Well Name: WELLER No. 1
C S/2 S/2 SE/4 6-20S-13W
Barton County, Kansas

Contractor: E. K. Edmiston Drilling Co., Inc.
501 First National Bank Building
Wichita, Kansas 67202

Casing Record: 8-5/8" at 760' with 400 sacks cement
4-1/2" at 3523' with 100 sacks cement

L O G

Measurements from top of Kelly Bushing

Sand	0 - 224
Shale and Sand	320
Sand and Shale	590
Shale and Red Bed	705
Red Bed and Shale	755
Anhydrite	785
Shale and Shells	1550
Shale and Lime	1850
Lime and Shale	2632
Shale and Lime	2795
Lime and Shale	3185
Lime	3528 RTD

RECEIVED
STATE CORPORATIONS COMMISSION

MAR 23 1966
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, E. K. Edmiston, President of E. K. Edmiston Drilling Co., Inc., hereby certifies on behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well, as reflected by the daily drilling reports.

E. K. EDMISTON DRILLING CO., INC.

By E. K. Edmiston
E. K. Edmiston, President

STATE OF KANSAS,
SS:
SEDGWICK COUNTY,

BE IT REMEMBERED that on this 17th day of June, 1965, before me, the undersigned, a Notary Public within and for said county and state, came E. K. EDMISTON, known to me to be the same person who executed the foregoing instrument as President and on behalf of E. K. Edmiston Drilling Co., Inc., and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

A. B. Barga
A. B. Barga, Notary Public

My commission expires
August 25, 1968

