


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County. Sec. 6 Twp. 20 Rge. 13 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____

Approx NE SE NW
Lease Owner Ruffin Oil Company
Lease Name Weber Well No. 1
Office Address c/o Rockwood Petroleum, 815 Douglas, Wichita,
Character of Well (Completed as Oil, Gas or Dry Hole) Ks.



Locate well correctly on above
Section Plat

Date Well completed 2-26 19 81
Application for plugging filed 2-26 19 81
Application for plugging approved 2-26 19 81
Plugging commenced 2-26 19 81
Plugging completed 2-26 19 81
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3500'
Show depth and thickness of all water, oil and gas formations:

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug: @ 750' w/40 sacks 50/50 pozmix 3% cc. thru drill pipe
Middle Plug: @ 300' w/25 sacks " " " " " " "
Top Plug: @ 40' w/10 sacks cement & $\frac{1}{2}$ sack hulls
10 sacks in Rat Hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.
Bill Draney (employee of owner) or ~~(owner or operator)~~
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Draney
P.O. Box 823 Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of February, 19 81

My commission expires 4-11-1982

L. L. M. Blaque
Notary Public
Wichita, Kansas

MAR - 2 1981
CONSERVATION DIVISION
Wichita, Kansas

3-2-81

DRILLERS' WELL LOG

DATE COMMENCED: February 18, 1981
 DATE COMPLETED: February 26, 1981

Ruffin Oil Co.
 WEBER #1
 Approx. NE 3/4 NW
 Sec. 6, T20S, R13W
 Barton County, Kas.

10 - 160' Sand w/ Shale Streaks
 160 - 258' Shale
 258 - 290' Sand
 290 - 761' Shale & Red Bed
 761 - 787' Anhydrite
 787 - 2750' Shale & Lime
 2750 - 3089' Lime & Shale
 3089 - 3093' Shale
 3093 - 3103' Lime & Shale
 3103 - 3120' Lime
 3120 - 3192' Shale
 3192 - 3202' Lime & Shale
 3202 - 3436' Lime
 3436 - 3471' Lime, Chert, Congl.
 3471 - 3500' Dolomite
 3500' RTD

ELEVATION: 1869 K.B.

FORMATION DATA

Anhydrite	761'
Howard	2750'
Topoka	2880'
Heebner	3089'
Toronto	3103'
Douglas	3120'
Br. Lime	3192'
Lansing K.G.	3202'
Base K.C.	3436'
Cherty Conglomerate	3448'
Arbuckle	3471'
RTD	3500'

Surface Pipe: Set used 2 1/2",
 2-5/8" pipe at 767' w/500 sacks
 50/50 pozmix, 2% gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Subscribed and sworn to before me this 27th day of February 1981.

My Comm. Expires:

4-11-1982

Bill Draney

Robert M. Hague
 Notary Public

RECEIVED
 CONSERVATION DIVISION

MAR - 2 1981

CONSERVATION DIVISION
 Topeka, Kansas