


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. E. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Barton County. Sec. 24 Twp. 20S Rge. 13W (E) (W)
Location as "NE/CNW%SW%" or footage from lines SE SE SW
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name RUBART Well No. 1
Office Address 800 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed September 7, 1958 19
Application for plugging filed September 7, 1958 19
Application for plugging approved September 7, 1958 19
Plugging commenced September 7, 1958 19
Plugging completed September 7, 1958 19
Reason for abandonment of well or producing formation is non productive in commercial quantities
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan - Gorham, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3555 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	204	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud from total depth to 200 feet - plug and 1/4 sack hulls at 200 feet - 25 sacks cement through drill pipe and mud to 40 feet another plug and 1/4th sack hulls with 10 sacks cement on top

RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1958
CONSERVATION DIVISION
Wichita, Kansas

9-10-58

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Quaker Drilling Co., Inc.
Address 800 Bitting Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul
800 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 9th day of September, 19 58

My commission expires August 10, 1961

Virginia Murrell
Notary Public.

PLUGGING
FILE SEC 24 T. 20 R. 13W
BOOK PAGE 128 LINE 16

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: August 29, 1958

Contractor: Quaker Drilling Co., Inc.

Completed: August 7, 1958

Rubart No. 1
SE SE SW Sec. 24-20S-13W
Barton County, Kansas

Elevation: 1862 KB

Casing Record:

Set 8 5/8 inch casing at 204 feet with 225 sacks pozmix

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil & Sand	110	Anhydrite	685
Hard Sand	120	Heebner	3090 -1236
Shale	150	Brown Lime	3220 -1358
Hard Sand	160	Lansing	3234 -1372
Shale	204	Base of Kansas City	3458 -1596
Shale and Shells	300	Conglomerate	3498 -1636
Red Bed	685	Rotary Total Depth	3555 -1693
Anhydrite	710		
Red Bed	1175		
Shale and Lime	1330		
Shale and Sandy Lime	1630		
Lime and Shale	2105		
Shale	2325		
Shale and Lime	2665		
Shale	2790		
Lime	2915		
Lime and Shale	3220		
Lime	3380		
Lime and Shale	3495		
Shale	3498		
Dolomite	3555		

RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1958
CONSERVATION DIVISION
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the Driller's Log on the well drilled in the SE SE SW of Section 24, Township 20 South, Range 13 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: Thomas M. McCaul
Thomas M. McCaul

SUBSCRIBED AND SWORN to before me a Notary Public this 9th day of September, 1958.

Virginia Mundell
Virginia Mundell, Notary Public

MY COMMISSION EXPIRES:
August 10, 1961

PLUGGING
FILE SEC 24 T 20 R 13W
BOOK PAGE 128 LINE 16