


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Barton County. Sec. 24 Twp. 20S Rge. 13 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NW NE  
Lease Owner Alva Oil Corporation  
Lease Name Schartz Well No. 1  
Office Address Fourth National Bank Bldg. - Wichita, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed November 17 19 59  
Application for plugging filed November 17 19 59  
Application for plugging approved November 17 19 59  
Plugging commenced November 17 19 59  
Plugging completed November 17 19 59  
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	263'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Broke down drill pipe. Set bottom plug @ 250' with 1/2 sacks hulls and 25 sacks cement. Set top plug @ 35' with 1/2 sack hulls and 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 25 1959

CONSERVATION DIVISION  
Wichita, Kansas

11-25-59

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company  
Address Box 173 - Russell, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
George A. Angle (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle  
580 4th Nat'l Bank Bldg. - Wichita  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November, 1959

Mapine Head

Notary Public.

My commission expires 11-17-62



DRILLERS LOG

No. 1 Schartz

CASING RECORD: 8 5/8" @ 261' w/175 sx cement  
 COMPANY: Alva Oil Corp.  
 CONTRACTOR: Red Tiger Drilling Co.  
 COMMENCED: November 9, 1959  
 COMPLETED: November 17, 1959  
 DESCRIPTION: NE NW NE  
 24-20S-13W  
 Barton County  
 Kansas  
 ELEVATION: 1855 DF  
 1858 RB  
 TOTAL DEPTH: 3525'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Gravel	0	235	
Shale	235	261	
Shale & Sand	261	320	
Red Bed Shells	320	585	
Red Bed & Shells	585	680	
Anhydrite	680	718	
Shale & Shells	718	1410	
Shale Shells	1410	1460	
Shale Lime	1460	1600	
Lime Shale	1600	1680	
Lime and Shale	1680	2075	
Lime Shale	2075	2135	
Shale Lime	2135	2335	
Shale & Lime	2335	2560	
Lime & Shale	2560	2790	
Lime Shale	2790	2915	
Lime & Shale	2915	3015	
Lime	3015	3115	
Shale & Lime	3115	3235	
Lime	3235	3390	
Lime Shale	3390	3466	
Chert	3466	3496	
Chert	3496	3505	
Chert & Sand	3505	3525	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

*George A. Angle*  
 George A. Angle

Subscribed and sworn to before me this 19th day of November, 1959.

*Maryne Head*  
 Notary Public

My Commission Expires:

11-17-62

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 25 1959  
 CONSERVATION DIVISION  
 Wichita, Kansas