

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County. Sec. 24 Twp. 20 Rge. 13 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE NE NW

Lease Owner Petroleum Energy, Inc.

Lease Name BATCHMAN Well No. 1

Office Address Suite 710 One Twenty Bldg., Wichita, Ks. 67202

Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed March 31 1978

Application for plugging filed March 31 1978

Application for plugging approved March 31 1978

Plugging commenced March 31 1978

Plugging completed March 31 1978

Reason for abandonment of well or producing formation _____


If a producing well is abandoned, date of last production
19 _____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3490

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug @ 420' with 40 sacks cement thru drill pipe.

Middle Plug at 240' with 25 sacks cement thru drill pipe.

Top plug @ 40' w/ $\frac{1}{2}$ sack hulls & 10 sacks cement.

2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

APR 06 1978 4-6-78

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.
Leonard Williamson (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson

Box 823 - Great Bend, Ks. 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of April, 1978

My commission expires April 11, 1978

Dorothy M. Nague
Notary Public.

DRILLERS' WELL LOG

DATE COMMENCED: March 25, 1978
DATE COMPLETED: March 31, 1978

Petroleum Energy, Inc.
BATCHMAN #1
SE NE NW Sec. 24-T20-R13W
Barton County, Ks.

0 - 210'	Sand
210 - 676'	Shale & Red Bed
676 - 700'	Anhydrite
700 - 1465'	Shale & Red Bed
1465 - 1550'	Shale & Lime Streaks
1550 - 3084'	Lime & Shale
3084 - 3088'	Shale
3088 - 3106'	Shale & Lim.
3106 - 3120'	Lime
3120 - 3201'	Shale
3201 - 3216'	Lime & Shale
3216 - 3438'	Lime
3438 - 3449'	Lime & Shale
3449 - 3490'	Lime, Shale, Chert
3490'	RTD

ELEVATION: 1857 K.B.

FORMATION DATA

Anhydrite	676
Heebner	3084
Toronto	3106
Douglas	3120
Br. Lime	3201
Kansas City	3216
Base K.C.	3438
Conglomerate	3449
RTD	3490

SURFACE PIPE: Set used 8-5/8" at 265' with 215' sacks common cement, 2% Gal, 3% ca.ch.

AFFIDAVIT

STATE OF KANSAS,
COUNTY OF BARTON) ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 14th day of April 1978.

Dorothy M. Hogue
Notary Public

My Comm. Expires:

April 11, 1978

RECEIVED
STATE OF KANSAS
APR 06 1978

MINERAL DIVISION
Kansas