

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-24,132-0000

LEASE NAME Schermuly

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-24

2310 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 24 TWP. 20 RGE. 13 (E or W)

LEASE OPERATOR Texas Energies, Inc.

COUNTY Barton

ADDRESS P. O. Box 947, Pratt, Kansas 67124

PHONE# () 316-672-7581 OPERATORS LICENSE NO. 5087

Date Well Completed 12-31-85

Character of Well _____

Plugging Commenced 12-31-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-31-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas office

Is ACO-1 filed? _____ If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	352	8 5/8	12/20/85	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set EZ Drill SV packer at 2647'. Cement with 100 sxs thixotropic; 50 sxs above packer; 50 sxs below packer. Job complete at 12:30 a.m. on 12-31-85. Spot 100 sxs 60/40 poz, 6% gel, 2% cc at 2400'. Job complete at 7 a.m. on 12-31-85. Plug well with 110 sxs 60/40 poz, 6% gel, 2% cc at 1900' & 377 sxs 60/40 poz, 1/4# flocele per sx. Circ. from 760' to surface. Job complete at 5:30p.m. (If additional description is necessary, use BACK of this form.) (on back)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149


Address P. O. Box 329, Pratt, Kansas 67124

STATE OF KANSAS COUNTY OF PRATT, ss.

Tracy Graven (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Tracy C. Graven

(Address) P. O. Box 329, Pratt, Kansas 67124



SUBSCRIBED AND SWORN TO before me this 14th day of January, 1986

Mary L. Tjaden
Notary Public

My Commission Expires: 3/22/88 RECEIVED
STATE CORPORATION COMMISSION

JAN 17 1986 1-17-86

Form CP-4
Revised 08-84

on 12-31-85 by Halliburton of Great Bend. State Plugger was out of the Hays, Kansas office.

RECEIVED
FEB 1 1986
STATE PLUGGER



Oilfield Services, Inc.

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

Schermuly #1-24
 NE NW SE Sec. 20-20S-13W
 Barton County, Kansas
 Commenced: 12-20-85
 Completed: 12-31-85
 API #15-009-24,132
 Operator: Texas Energies, Inc.

Depth		Formation	Remarks
From	To		
0	360	Sand, Shale	Ran 8 joints (337') new, 23#, 8 5/8" surface casing. Set at 352' with 100 sxs lite and 100 sxs Common, 2% gel, 3% cc. Plug down at 9:15 p.m. 12-20-85. Job by Halliburton of Great Bend. Cement did not circulate.
360	423	Clay, Sand	
423	1105	Clay	
1105	2931	Lime, Shale T.D.	
			Pumped 60 sxs Common, 2% gel, 3% cc through 1" tubing from 50' to surface. Did circulate. Job complete at 12:00 a.m. 12-21-85 by Halliburton of Great Bend.
			Lost circulation at 2900'.
			Squeeze with 150 sxs Thixotropic. Spotted at 2901'. Job complete at 7:15 p.m. 12-27-85 by Halliburton of Great Bend.
			Squeeze with 200 sxs 60/40 poz, preceded by 500 gal. flow check. Spotted at 2900'. Job complete at 3:00 a.m. 12-28-85 by Halliburton of Great Bend.
			Squeeze with 50 sxs 60/40 poz, 6% gel, 2% cc. Spotted at 2910'. Job complete at 8:00 p.m. on 12-28-85 by Halliburton of Great Bend.
			Squeeze with 25 sxs 60/40 poz, 6% gel, 3½% cc. Spotted at 2900'. Job complete at 12:45 a.m. on 12-29-85 by Halliburton of Great Bend.
			Squeeze with 50 sxs 60/40 poz, 6% gel, 3½% cc. Spotted at 2430'. Job complete at 6:15 a.m. on 12-29-85 by Halliburton of Great Bend.
			Squeeze with 50 sxs 60/40 poz, 6% gel, 4% cc. Spotted at 2190'. Job complete at 12:00 p.m. 12-29-85 by Halliburton of Great Bend.

RECEIVED
 STATE CORPORATION COMMISSION

JAN 17 1986

CONSERVATION DIVISION
 WASHINGTON, KANSAS

Driller's Well Log
Schermuly #1-24
Barton County, Kansas
Operator: Texas Energies, Inc.

15.009.24132.0000

Set EZ Drill SV Packer at 2647'. Cement with 100 sxs Thixotropic; 50 sxs above packer; 50 sxs below packer at 12:30 a.m. Spot 100 sxs 60/40 poz, 6% gel, 2% cc at 2400'. Job complete at 7:00 a.m. 12-31-85. by Halliburton of Great Bend.

Plug well with 110 sxs 60/40 poz, 6% gel, 2% cc at 1900' and 377 sxs 60/40 poz, 1/4# flocele per sx. Circulated from 760' to surface. Job complete at 5:20 p.m. 12-31-85 by Halliburton of Great Bend. State plugger was out of the Hays, Kansas office.

STATE OF KANSAS)
) SS
COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

Arnie Little
ARNIE LITTLE, PRESIDENT



Mary L. Tjaden
NOTARY PUBLIC

My Commission Expires:

3/22/88

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1986
CONSERVATION DIVISION