

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-009-24,132.0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Texas Energies, Inc. OPERATORS LICENSE NO. 5087

ADDRESS P. O. Box 947..Pratt, Kansas 67124 PHONE # () 316-672-7581

LEASE (FARM) Schermuly WELL NO. 1-24 WELL LOCATION NE NW SE COUNTY Barton

SEC. 24 TWP. 20 RGE. 13 (E) or (W) TOTAL DEPTH 2931 PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A XX SWD or INJ WELL _____ DOCKET NO. 12-31-85

SURFACE CASING SIZE 8 5/8" SET AT 352 CEMENTED WITH 200 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set E-Z Drill SV Packer at 2647'. Cement with 100 sxs thixotropic; 50 sxs above packer, 50 sxs below packer. Spot 100 sxs 60/40 poz, 6%

get, 2% cc at 2400'. Plug well with 110 sxs 60/40 poz, 6% gel, 2% cc at 1900' & 377 sxs 60/40 poz 1/4# flocele per sx. circ.(If additional space is needed use back of form) from 760' to surface.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN _____ at once

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Tony Ernst (Toolpusher Rig 1) PHONE # () 316-672-7514

ADDRESS P. O. Box 329, Pratt, Kansas 67124

PLUGGING CONTRACTOR Wheatstate Oilfield Services, Inc. LICENSE NO. 5149

ADDRESS P. O. Box 329, Pratt, Kansas 67124 PHONE # () 316-672-7514

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Tracy C. Shaver
(Operator or Agent)

JAN 17 1986

DATE: 1/14/86

CONSERVATION DIVISION
WICHITA, KANSAS