


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barton County. Sec. 36 Twp. 20S Rge. (E) 13W (W)  
Location as "NE/CNW/SW" or footage from lines NE SE NE  
Lease Owner Circle Oil Company, Inc.  
Lease Name LONNON Well No. 4  
Office Address 500 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 12, 1966  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced September 12, 1966  
Plugging completed September 12, 1966  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Donald Truan)

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3566 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	218'	8-5/8"	9/6/66	-----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy Mud from Total Depth to 210 feet; Hull Plug and HOWCO Plug and 25 sacks cement through the drill pipe; Mud to 40 feet; 1/2 sack Halls and Plug bridged with Kelly and 10 sacks cement to base of cellar; 2 sacks cement in rat hole. Job completed at 11:00 P.M.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 20 1966

CONSERVATION DIVISION  
Wichita, Kansas

9-20-1966

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co., Inc.  
Address 500 Bitting Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Lawrence F. Gray

\_\_\_\_\_(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Lawrence F. Gray

500 Bitting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of September, 19 66

My commission expires November 26, 1966

Louise F. Whitted  
Louise K. Whitted - Notary Public.

DRILLERS LOG

LONNON NO. 4

CASING RECORD:	COMPANY:	Circle Oil Co.	DESCRIPTION:
8-5/8" @ 218' w/225 sax cement	CONTRACTOR:	Sage Drilling Co.	NE SE NE Sec. 36-20S-13W Barton Co., Kansas
TOTAL DEPTH: 3566'	COMMENCED:	September 6, 1966	ELEVATION: 1863KB
	COMPLETED:	September 12, 1966	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	15	
Sand	15	110	
Shale	110	280	
Red Bed	280	681	
Anhydrite	681	703	
Shale	703	1145	
Shale & Lime	1145	1490	
Lime & Shale	1490	2030	
Shale & Lime	2030	2795	
Lime & Shale	2795	2945	
Lime	2945	3123	
Shale & Lime	3123	3215	
Lime & Shale	3215	3245	
Lime	3245	3297	
Lime & Shale	3297	3406	
Lime	3406	3445	
Cherty Lime	3445	3566	

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 SEP 20 1966  
 CONSERVATION DIVISION  
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING COMPANY, INC.

By Lawrence F. Gray  
 Lawrence F. Gray

Subscribed and sworn to before me this 15th day of September, 1966.

Louise K. Whitted  
 Louise K. Whitted, Notary Public

My commission expires:  
 November 26, 1966