


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 35 Twp. 20S Rge. 13W (E) (W)
Location as "NE/CNW%SW%" or footage from lines NE NE NW
Lease Owner x ALPINE OIL & ROYALTY CO., INC.
Lease Name Yeary Well No. 1
Office Address 800 Bitting Building, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed June 8, 1961 19
Application for plugging filed June 8, 1961 19
Application for plugging approved June 8, 1961 19
Plugging commenced June 8, 1961 19
Plugging completed June 8, 1961 19
Reason for abandonment of well or producing formation non-productive
If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3581 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	XXXX 250'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from 3581 feet to 240 feet - 1/4th sack hulls and plug with 25 sacks through drill pipe then heavy mud to 35 feet - 1/2 sack hulls and 10 sacks cement and 2 sacks cement below plow depth in rat hole
Completed at 4:00 P. M.

RECEIVED
STATE CORPORATION COMMISSION

AUG 8 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Quaker Drilling Co., Inc.
Address 800 Bitting Building, Wichita, Ks.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas M. McCaul

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul
800 Bitting Building, Wichita, Ks.

(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of August, 19 63

My commission expires August 10, 1965

[Signature]
Notary Public.

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: 5-31-61

Contractor: Quaker Drilling Co., Inc.

Completed: 6-8-61

Yearly No. 1
NE NE NW Sec. 35-20S-13W
Barton County, Kansas

Elevation: 1881 K.B.

Production: I & A

Casing Record

8 5/8 inch casing set at 250 feet with 225 sacks cement

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil & Sand	187	Heebner	3137 -1256
Shale	250	Brown Lime	3258 -1377
Red Bed, Shale and Sand	714	Lansing	3272 -1391
Anhydrite	735	Base of KC	3498 -1617
Shale and Shells	1665	Conglomerate	3510 =1629
Lime and Shale	2955	Rotary Total	
Lime	3040	Lepty	3581 -1700
Lime and Shale	3295		
Lime	3320		
Lime and Shale	3365		
Lime	3458		
Lime and Shale	3570		
Shale and Chert	3581		

RECEIVED
STATE CORPORATION COMM.

AUG 8 1963

CONSERVATION DIVISION
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the NE NE NW of Section 35, Township 20 South, Range 13 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: *Thomas M. McCaul*

SUBSCRIBED AND SWORN TO BEFORE ME A Notary Public this 15th day of June, 1961.

Virginia Mandell
Virginia Mandell, Notary Public

MY COMMISSION EXPIRES:
August 10, 1961